

Site Accessibility Evaluation



**Path of Travel Bus Stop
Accessibility
PU18-0091**

**Galley Road / Peterson
Road
Cimarron Hills, CO 80915**

Public Right of Way

***Inspection Date: 09/13/2018
Inspector: David Mejia***

Prepared By



**(719) 520 - 6866
www.elpasoco.com**

Path of Travel / Curb Ramps

Finding: 1

No diagonal or corner curb ramp exists.

2010 ADAS Section 406.3
Where provided, curb ramp flares shall not be steeper than 1:10.

Citation:

2010 ADAS Section: 406.3

As Built:

Curb ramps non existant

Recommendation:


Design and construct curb ramp for accessible path of travel. See 2010 ADAS section 4.06 for specificaitons and compliance. Maximum running slope of 1:12 (8.33%) and maximum cross slope of 1:48 (2.08%). if provided, curb ramp flares shall not be steeper that 1:10 (10%)

Notes:

Corrective Action: Department of Public Works submitted and completed 2 compliant curb ramps along with 215 linear feet of 6 feet wide detachable sidewalk on 8/31/2018



Finding 204417 Main Photo



Finding #1 Additional Finding Photos



Finding 204417 Additional Photo



Finding 204417 Additional Photo



Finding 204417 Additional Photo



Finding 204417 Additional Photo



Finding 204417 Additional Photo



Finding 204417 Additional Photo



Finding 204417 Additional Photo